

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21635-00-00
Spot: NENWNW Sec/Twnshp/Rge: 1-25S-15W
330 feet from N Section Line, 990 feet from W Section Line
Lease Name: R D WATERS Well #: 1-C
County: STAFFORD Total Vertical Depth: 4421 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	297		WITH 225 SX CMT
PROD	5.5	4412	1930	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/1988 9:30 AM
Plug Co. License No.: 4635 Plug Co. Name: GREAT BEND CASING PULLERS, INC.
Proposal Rcvd. from: GARY BURKE Company: GREAT BEND CASING PULLERS, I Phone: (316) 793-9711

Proposed Plugging Method: PBTD 4400'. SHOT AT 2000' & 1930'. 1ST PLUG SAND BACK TO 4350' & DUMP 5 SX CMT ON TOP OF SAND THROUGH BAILER. 2ND PLUG PUMP 4 SX HULLS, 10 SX GEL, 50 SX CMT, 10 SX GEL, 1 SX HULLS, RELEASE 8 5/8" WIPER PLUG & PUMP 100 SX CMT

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/1988 10:30 AM KCC Agent: DUANE RANKIN

Actual Plugging Report:

1ST PLUG SANDED BACK TO 4350' & DUMPED 5 SX CMT ON TOP OF SAND THROUGH BAILER. 2ND PLUG PUMPED INTO 8 5/8" SURFACE CASING WITH 400# HULLS, 10 SX GEL, 50 SX CMT, 10 SX GEL, 100# HULLS, RELEASED 8 5/8" WIPER PLUG & PUMPED 100 SX CMT. PUMPING PRESSURE 0-700 PSI & SHUT IN 300 PSI.

Perfs:

Top	Bot	Thru	Comments
4402	4404		

Remarks: USED 60/40 POZMIX 6% GEL BY B.J. TITAN.

Plugged through: CSG

RECEIVED

JAN 25 2012

KCC WICHITA

District: 01

Signed

Duane Rankin / SD

(TECHNICIAN)