

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-10124-00-00  
Spot: SE Sec/Twnshp/Rge: 12-25S-16W  
1324 feet from S Section Line, 1427 feet from E Section Line  
Lease Name: MILLER D Well #: 1  
County: EDWARDS Total Vertical Depth: 4335 feet

Operator License No.: 32713  
Op Name: SAND POINT LLC  
Address: 5909 NW EXPRESSWAY, STE 490  
OKLAHOMA CITY, OK 73132

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4200		WITH 2 SX CMT
SURF	8.625	317		WITH 225 SX CMT
PLG	5.5	4310		
PROD	5.5	4335	1780	WITH 115 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/13/2011 8:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4200' WITH 2 SX CMT. PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/13/2011 9:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

\*\*WELL WAS SQUEEZED @ 2452'-3126' WITH 600 SX CMT. SQUEEZED @ 2700-3100' WITH 100 SX CMT.\*\* SET CIBP@ 4200' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 1074' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 365' WITH 50 SX CMT. 3RD PLUG T 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4249	4258		KINDERHOOK
4232	4242		MISSISSIPPI

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

*Richard M. Lacey*

(TECHNICIAN)

RECEIVED  
DEC 19 2011  
KCC DODGE CITY

RECEIVED  
JAN 06 2012  
KCC WICHITA

*1/22/12*