

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20947-00-00
Spot: SWSENW Sec/Twnshp/Rge: 28-22S-18E
2985 feet from S Section Line, 3638 feet from E Section Line
Lease Name: COLGIN Well #: 2
County: ANDERSON Total Vertical Depth: 1578 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1567		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2011 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RUN CMT BOND LOG, LOC TOP CMT, RIH W/2 3/8" TBG SPOT 50' CMT PLUG AT BTM OF CSG, PERF ABOVE, PUMP GEL SPACER, PUMP 100' CMTPLUG @700', SHOOT CSG OFF ABOVE CEMENT, POOH CSG, RBIH W/TBG PUMP GEL SPACER, THEN CMT FROM 300' TO SURFACE. RETURN AT A LATER DATE, DIG DOWN & CUT OFF CSG BELOW PLOW DEPTH.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 11/07/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

ON 11/7/2011 RUN 2-INCH PIPE TO 1550 FEET IN 4-1/2 INCH AND PLACE 100 FOOT PLUG. THEN PLACE 100 FOOT PLUG AT 700 FEET AND FROM 300 FEET TO SURFACE. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 63 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
1567	1578		ARBUCKLE OPEN

RECEIVED
JAN 4 2012
KCC Chanute Dist. #3

RECEIVED
KANSAS CORPORATION COMMISSION
JAN - 9 - 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks:
Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

RECEIVED: Reltd. to D.3 per report 1/9/12.
JAN 19 2012
KCC WICHITA
1/23/12