

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-22542-00-00  
Spot: SESENW Sec/Twnshp/Rge: 28-22S-18E  
2984 feet from S Section Line, 3037 feet from E Section Line  
Lease Name: COLGIN Well #: 3  
County: ANDERSON Total Vertical Depth: 1562 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	40		
PROD	4.5	1550		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2011 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8:TUB, WASH TO BTM (TD IN OTHER WELLS IS 1556'+/-. RUN CMT BOND LOG, LOC TOP CMT, IF CMT'D TO SURFACE PUMP 50' CMT PLUG AT BTM, GEL SPACER, PUMP 50' CMT PLUG @700', GEL SPACER CMT FROM 300' TO SURFACE. IF NOT CMT'D TO SURFACE, PERF ABOVE CMT PLUG AS NOTED AND CIRC CMT ON BACKSIDE OF PROD CSG TO SURFACE + CMT INSIDE IF CAN'T EST CIRC. SHOOT OFF AND PLUG AS NOTED.

Plugging Proposal Received By: LEVI SHORT WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/01/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

ON 11/21/2011 RUN 2-INCH PIPE TO 1550 FEET IN 4-1/2 INCH AND PLACE 50 FOOT PLUG. ON 12/1/2011 RUN 2-INCH TO 700 AND PLACE 100 FOOT PLUG. PLACE 2-INCH AT 300 FEET AND FILL TO SURFACE WITH CEMENT. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 73 SACKS OF CEMENT.

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN-9-2012  
CONSERVATION DIVISION  
WICHITA, KS

RECEIVED

JAN 4 2012

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED

JAN-1-9-2012

KCC WICHITA

Ret'd. to D.3 per reg. 1/9/12.  
Form CP-213  
✓ 1/23/12