

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20508-00-00
Spot: SWNESW Sec/Twnshp/Rge: 28-22S-18E
1612 feet from S Section Line, 3652 feet from E Section Line
Lease Name: LAY Well #: 1
County: ANDERSON Total Vertical Depth: 1551 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	40		
PROD	4.5	1546	100	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2011 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: CMT BOND LOG (4/23/03), SHOWS TOP OF CMT @1028', PERF JUST ABOVE & TRY TO EST CIRC, IF CAN'T, SHOOT OFF CSG & POOH. RIH W/2 3/8" TBG TO BTM, PUMP 50' CMT PLUG, GEL SPACER, 100' CMT PLUG @1040'+/-, GEL SPACER, CMT FROM 300' TO SURFACE. IF CIRC, CMT BACK SIDE OF CSG AND REST AS NOTED.

Plugging Proposal Received By: LEVI SHORT Witness Type: PARTIAL
Date/Time Plugging Completed: 10/31/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

ON 10/26/2011 RUN 2-INCH PIPE TO 900 FEET IN 4-1/2 INCH AND PLACE 100 FOOT PLUG. ON 10/31/2011 RUN 2-INCH AT 300 FEET AND FILL TO SURFACE WITH CEMENT. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 98 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
1546	1550		OPEN HOLE

RECEIVED

JAN 3 2012 LS

KCC Chanute Dist. #3

RECEIVED
KANSAS CORPORATION COMMISSION

JAN - 9 2012

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Levi Short

(TECHNICIAN)

RECEIVED

JAN 19 2012

KCC WICHITA

Rel'd. to D. 3 per reg. 1/19/12.
Form CP-2/3

1/23/12