

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-20542-00-00  
Spot: NWNESW Sec/Twnshp/Rge: 28-22S-18E  
2304 feet from S Section Line, 3646 feet from E Section Line  
Lease Name: LAY Well #: 2  
County: ANDERSON Total Vertical Depth: 1563 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	40		
PROD	4.5	50	50	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/26/2011 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: CMT BOND LOG TO FIND TOP OF CMT PERF ABOVE & TRY TO CIRC, IF NOT, RIH W/2 3/8" TBG TO BTM, PUMP 50' CMT PLUG, GEL SPACER TO 50' BELOW PERFS. SHOOT CSG OFF, POOH SAME RBIH W/TUBING, PUMP 100' CMT PLUG ABOVE LAST GEL SPACER, THEN CMT FROM 300' TO SURFACE. 1054

Plugging Proposal Received By: LEVI SHORT Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/31/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

ON 10/26/2011 RUN 2-INCH PIPE TO 1563 FEET IN 4-1/2 INCH AND PLACE 100 FOOT PLUG. ON 10/31/2011 RUN 2-INCH TO 750 AND PLACE 100 FOOT PLUG. PLACE 2-INCH AT 300 FEET AND FILL TO SURFACE WITH CEMENT. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 66 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
1546	1550		OPEN HOLE

RECEIVED

JAN 3 2012 LS

KCC Chanute Dist. #3

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN - 9 2012  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED Rtd. to D. 3 per rept. 1/9/12. Form CR-2/3

JAN-19-2012

KCC WICHITA

1/23/12