

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20574-00-00
Spot: SENESW Sec/Twnshp/Rge: 28-22S-18E
1632 feet from S Section Line, 2983 feet from E Section Line
Lease Name: LAY Well #: 3
County: ANDERSON Total Vertical Depth: 1553 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1549		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2011 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: CMT BOND LOG TO FIND TOP OF CMT PERF ABOVE & TRY TO CIRC, IF SO, RIH W/2 3/8" TBG TO BTM, PUMP 50' CMT PLUG, GEL SPACER, CIRC CMT ON BACK SIDE OF PROD CSG + INSIDE SAME. IF CAN'T CIRC, SHOOT CSG OFF, POOH SAME RBIH W/TUBING, PUMP 100' CMT PLUG AT SHOT PT, GEL SPACER, THEN CMT FROM 300' TO SURFACE.

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 10/28/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

ON 10/21/2011 RUN 2-INCH PIPE TO 1550 FEET IN 4-1/2 INCH AND PLACE 100 FOOT PLUG. THEN PLACE 50 FOOT PLUG AT 700 FEET AND FROM 300 FEET TO SURFACE. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 63 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
1549	1553		OPEN HOLE

RECEIVED
KANSAS CORPORATION COMMISSION
JAN - 9 2012
CONSERVATION DIVISION
WICHITA, KS

RECEIVED

JAN 3 2012 LS


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED Ret'd. to D.3 per reg. 1/9/12.
Form CP-2/8

JAN 19 2012

KCC WICHITA

1/23/12