

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20528-00-01
Spot: SENWSW Sec/Twnshp/Rge: 28-22S-18E
1629 feet from S Section Line, 4306 feet from E Section Line
Lease Name: SPENCER Well #: 3 (WDW)
County: ANDERSON Total Vertical Depth: 1554 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	40		10 SX
PROD	4.54	1548	100	100 SX

Well Type: EOR UIC Docket No: E24985.1 Date/Time to Plug: 10/21/2011 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RUN CMT BOND LOG, LOC TOP OF CMT, PERF ABOVE, CIRC, IF CAN'T, IF NOT SHOOT OFF CSG, POOH SAME, RIH W/2 3/8" TBG, PUMP 50' CMT PLUG AT BTM, GEL SPACER, 100' CMT @ SHOT PT, GEL SPACER, CMT FROM 300' TO SURFACE. IF CIRC, PUMP CMT BACK SIDE OF PROD CSG, CMT AS NOTED.

Plugging Proposal Received By: LEVI SHORT Witness Type: PARTIAL
Date/Time Plugging Completed: 10/25/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

ON 10/21/2011 RUN 2-INCH PIPE TO 1340 FEET IN 4-1/2 INCH AND PLACE 100 FOOT PLUG. THEN PLACE 50 FOOT PLUG AT 500 FEET AND FROM 300 FEET TO SURFACE. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 86 SACKS OF CEMENT. RETURNED ON 10/25/2011 AND TOPPED OFF WELL FROM 300 FEET TO SURFACE WITH 39 SACKS OF CEMENT. TOTAL CEMENT USED FOR BOTH PROCEDURES WAS 125 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
1548	1554		OPEN HOLE

RECEIVED
JAN 3 2012 LS
KCC Chanute Dist. #3

RECEIVED
KANSAS CORPORATION COMMISSION
JAN - 9 2012
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Levi Short

(TECHNICIAN)

RECEIVED Ret'd. to D. 3 per req't. 1/9/12.
Form CP-2/3

JAN 19 2012

KCC WICHITA

1/23/12
cc to UIC 1/24/12