

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-20575-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 28-22S-18E  
2989 feet from S Section Line, 4319 feet from E Section Line  
Lease Name: COLGIN Well #: 1  
County: ANDERSON Total Vertical Depth: 1562 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	40		
PROD	4.5	1556		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/07/2011 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: RUN CMT BOND LOG, LOC TOP CMT, PERF ABOVE, CIRC, RIH TBG TO TD, PUMP 50' CMT PLUG, GEL SPACER, CIRC AMT AT PERFS ON BACK SIDE OF CSG AND INSIDE SAME TO SURF. IF NO CIRC, SHOOT CSG OFF, POOH SAME, CMT AS NOTED + 100' AT SHOT PT, GEL SPACER, CMT FROM 300' TO SURFACE.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE  
Date/Time Plugging Completed: 11/07/2011 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

ON 11/7/2011 RUN 2-INCH PIPE TO 1550 FEET IN 4-1/2 INCH AND PLACE 100 FOOT PLUG. THEN PLACE 100 FOOT PLUG AT 700 FEET AND FROM 300 FEET TO SURFACE. GEL SPACER WAS PLACED BETWEEN CEMENT PLUGS. USE TOTAL OF 63 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
1556	1562		ARBUCKLE OPEN

RECEIVED

JAN 4 2012

KCC Chanute Dist. #3


RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN - 9 2012  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED Ret'd. to D.3 per req. 1/9/12  
Form CP-213

JAN 19 2012

KCC WICHITA

1/23/12