

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21042-00-00
Spot: NENESE Sec/Twnshp/Rge: 14-16S-20W
2333 feet from S Section Line, 332 feet from E Section Line
Lease Name: HUBBS Well #: 3
County: RUSH Total Vertical Depth: 3955 feet

Operator License No.: 34004
Op Name: SAXON OIL COMPANY
Address: 11111 KATY FWY #900
HOUSTON, TX 77079

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	663		WITH 350 SX CMT
PROD	4.5	3951	0	WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2012 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MARK BIEKER Company: SAXON OIL Phone: (832) 900-4460

Proposed Plugging Method: CASING COLLAPSED @ 1950'. BOND LOG SHOWED CEMENT FROM 650' TO 1390'. PERFORATE 4 1/2" @ 600'. RUN TBG TO 1950' & CIRCULATE CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2012 9:50 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

****CASING COLLAPSED @ 1950'. BOND LOG SHOWED CMT FROM 650' TO 1390'.****
PERFORATED 4 1/2" @ 600'. RAN TBG TO 1949' & PUMPED 260 SX CMT.
CIRCULATED CMT UP 4 1/2" BUT DID NOT HAVE VALVE ON 4 1/2" TO SHUT IN.
GOOD CIRCULATION UP 8 5/8" X 4 1/2" BUT NO CMT. PULLED TBG TO 620' &
PUMPED 90 SX CMT CIRCULATING CMT UP 8 5/8" X 4 1/2" ANNULUS. PULLED TBG
OUT OF HOLE & TOPPED OFF BOTH STRINGS WITH 10 SX CMT.

RECEIVED
JAN 10 2012
1-10-12
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
JAN 06 2012
KCC DODGE CITY

Form CP-23

1/23/12