

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-00078-00-00
Spot: NW Sec/Twnshp/Rge: 24-29S-35W
1290 feet from N Section Line, 1320 feet from W Section Line
Lease Name: BLACKWELDER G D Well #: 1
County: GRANT Total Vertical Depth: 2815 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA,
Address: 5205 N O CONNOR BLVD
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	638		WITH 100 SX CMT
PROD 7		2535	673	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/16/2011 11:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: WELL HAS SAND FILL FROM 1400'. SAND PUMP WELL TO GET AS LOW AS POSSIBLE. PERFORATE 7" & SPOT 100 SX CMT. PERFORATE 7" @ 660' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2011 11:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

WELL HAS SAND FILL TO 1400 SAND PUMPED WELL TO 1550'. 7" CASING HAS TIGHT SPOT BETWEEN 900' & 1000'. PERFORATED 7" @ 1500'. RIH W/TBG TO 1500' & SPOTTED 100 SX CMT. LOST CIRCULATION TOWARD THE END. LET SET 2 HRS & TAGGED TOC @ 1137'. PRESSURE TESTED 7" CASING. PUMPED INTO AT 3 BBL/M @ 100 PSI. SDON. 12/19/11: FLUID LEVEL @ 50'. RIH W/TBG & PACKER TO 800' TO TEST 7" CASING BELOW 800'. NEVER HELD. MOVED PACKER TO 900', NEVER HELD. MOVED TO 1000', CASING HELD OK BELOW PACKER. POH W/TBG & PACKER TO 700'. INSTALLED TBG HEAD & TESTED 7" CASING ABOVE 700'. NEVER HELD. SIF SNOW STORM. 12/21/11: SHOT 7" CASING AT 673'. POH W/CASING. RIH W/ TBG TO 682'. PUMPED 150 SX CMT AT 682'. PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2679			UPPER FT. RILEY
2612			WINFIELD
2569			LOWER KRIDER
2548			UPPER KRIDER
2523			HERRINGTON

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

RECEIVED
JAN 10 2012
KCC WICHITA

District: 01

RECEIVED
JAN 05 2012
KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

Form CP 2/3

1/23/12