

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

X
API Well Number: 15-195-00356-00-01
Spot: E2SWSE Sec/Twnshp/Rge: 22-12S-21W
660 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KING OWWO Well #: 2
County: TREGO Total Vertical Depth: 4035 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3900		
SURF	8.625	235		200 SX
PROD	5.5	4035		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/02/2012 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN Phone: (800) 433-9047

Proposed Plugging Method: Ordered 425 sx 60/40 poz 4% gel cement, 500# hulls, 11 sx gel Perforated @2200', 1604', 905', and 230'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/10/2012 2:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3562', pumped 11 sx gel followed by 75sx cmt w/200# hulls
Pulled tubing to 2250' and pumped 100 sx cmt
Pulled tubing to 1300' and circulated w/ 150 sx cmt w/200# hulls
POOH. Topped off w/35 sx cmt
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3953	3958		ARBUCKLE
3848	3852		MARMATON
3543	3768		LKC
3528	3532		TORONTO

Remarks: QUALITY OIL WELL CEMENTING #564

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

JAN 12 2012

Form CP-2/3

✓ 1/23/12

RECEIVED
JAN 18 2012
1-10-12
KCC WICHITA