

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01324-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 18-8S-16W
2993 feet from S Section Line, 2350 feet from E Section Line
Lease Name: CHESNEY Well #: C 2
County: ROOKS Total Vertical Depth: 3200 feet

Operator License No.: 30821
Op Name: HITSCHMANN, CRAIG & RONDA DBA
Address: PO BOX 308
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	68		35 SX
PROD	4.5	3200		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/06/2012 9:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: CRAIG HITSCHMANN Company: C & R OIL Phone: (785) 885-8042

Proposed
Plugging
Method:

Perforate 2 holes each @ 1150' and 750'. Order out 350sx 60/40 poz mix 4% gel w/500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2012 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

LK perforated 2 holes each @ 1150', 750'. Ran tubing to 2034' hard bridge unable to get thru. Copeland Acid & Cement pumped 100 sx cement, pulled tubing to 750' & pumped 50 sx, cement circulated. P.T.O.H. Squezzed 10sx cement Max 400# SIP 400#. Hooked up to backside instant 300#.

Remarks:

Plugged through: TBG

RECEIVED
JAN 10 2012
KCC WICHITA

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

Form CP-2/3

✓ 1/23/12

JAN 13 2012