

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24886-00-00
Spot: W2NWNE Sec/Twnshp/Rge: 32-16S-13W
790 feet from N Section Line, 2310 feet from E Section Line
Lease Name: MATER Well #: 1
County: BARTON Total Vertical Depth: 3430 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	409		250 SX
T1	2.375	3425		
PROD	4.5	3428		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/04/2012 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: LD DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 500 sx 60/40 pos 4% gel, 400# hulls

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/04/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sx cement. Casing parted at 500'. Pulled casing . Ran tubing to 870'. Perfed out bottom of tubing at 875'. Ran tubing to 1590'. Perfed out bottom of tubing at 1600'. Tied to tubing and pumped 100 sx cement w/200# hulls. Pulled tubing to 900'. Pumped 40 sx cement w/100# hulls. Pulled tubing to 500' and circulated with 190 sx cement w/100# hulls. POOH. Hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3320	3324		
3277	3282		
3207	3212		
3156	3164		

RECEIVED
JAN 11 2012
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

JAN 09 2012

✓ 1/23/12