

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-16243-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 6-17S-13W
336 feet from S Section Line, 4631 feet from E Section Line
Lease Name: F L PUTNAM B Well #: 1
County: BARTON Total Vertical Depth: 3489 feet

Operator License No.: 4871
Op Name: HITSCHMANN, CURTIS LEE DBA CURT
Address: PO 8
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	0	0	unknown
PROD	5.5	3419	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2011 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMAN Company: CURT'S OIL Phone: _____

Proposed Plugging Method: Emergency plug. Rig over hole.
Ordered 350 sx 60/40 poz 4% gel cmt, 800# hulls

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated @1450', 930', 600', 150'.
Ran tubing to 3000'. Pumped 200 sx cmt w/400# hulls.
Pulled tubing to 1450'. Pumped 150 sx cmt w/400# hulls.
Cement circulated to surface. POOH
Tied to surface and pumped 35 sx cmt. Circulated up casing. Shut-in.

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

RECEIVED
JAN 11 2012
KCC WICHITA

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CM

Form CP-2/3

JAN 09 2012

✓ 1/23/12