

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20728-00-00
Spot: SESWNE Sec/Twnshp/Rge: 7-16S-10W
2968 feet from S Section Line, 1525 feet from E Section Line
Lease Name: HARBACEK Well #: 6
County: ELLSWORTH Total Vertical Depth: 3365 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	306		180 SXS CMT
PROD	5.5	3364		100 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/09/2012 11:00 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OIL WELL SERVICE
Proposal Rcvd. from: JAMES SCHOENBERGER Company: _____ Phone: (785) 324-2169

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 01/09/2012 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, THIS WELL HAS HAD NUMEROUS SQUEEZE JOBS PERFORMED--(5). MILLED DOWN TO 1380', RUN CEMENT BOND LOG--TOC @ 1100'. PERFORATE AT 1050'. RUN TUBING TO 1353' AND PUMP 20 SX'S COMMON CEMENT. PULL TUBING TO 1050' AND PUMP 35 SX'S COMMON CEMENT. LET SET FOR APPROX 1.5 HR'S AND TAG WITH WIRELINE @ 846'. PERFORATE AT 360'. RUN TUBING TO 360' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF

Perfs:

Top	Bot	Thru	Comments
3364	3365	OH	

RECEIVED
JAN 19 2012
KCC WICHITA

RECEIVED
JAN 19 2012
KCC WICHITA

Remarks: QUALITY WELL CEMENT TICKET #563. THE PERFORATORS TICKET #6071.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

✓ 1/23/12

JK