


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-169-00726-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County, Sec. 20 Twp. 14 Rge. 2 (E) W. (W)
Location as "NE/CNW%SW%" or footage from lines NW SW SW
Lease Owner West Supply Co., Inc.
Lease Name Van Ness #1 Well No. _____
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5-26-58 19____
Plugging completed 6-4-58 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3285 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	175'	none
				7"	3315'	2648'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3285' and found it open.
Filled w/sand to 3228' and ran 6 sacks of cement with dump bailer. Pulled 7" casing. Cleared hole and bailed mud to 160', set a 10' rock bridge and ran 25 sacks of cement. Mudded the hole to 17', set a 5' rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
06-06-58
JUN 6 1958

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE ^{SWIDE} ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of June, 1958

Thomas J. Duggin
Notary Public.



PLUGGING
FILE SEC. 20 T. 14 R. 2W
BOOK PAGE 99 LINE 4

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: C. C. Nelson Drilling Company
 FARM: Van Ness #1
 LOCATION: NW SW SW
 Section 20-14-2W
 Saline County
 COMMENCED: January 16, 1945
 COMPLETED: February 12, 1945 Rotary
 February 19, 1945 Cardwell
 ELEVATION: 1268 feet

0	to	185	Surface Sand
185	to	450	Shale and shells
450	to	580	Lime
580	to	750	Sandy lime
750	to	1500	Shale and shells
1500	to	1905	Lime
1905	to	2000	Shale
2000	to	2610	Lime
2610	to	2630	Shale
2630	to	2665	Conglomerate
2665	to	2670	Chat
2670	to	2730	Shale
2730	to	2750	Chert and lime
2750	to	2780	Chat and chert
2780	to	2900	Chert and lime
2900	to	2995	Lime
2995	to	3080	Shale
3080	to	3170	Lime
3170	to	3245	Shale
3245	to	3373	Lime
3373	to	3375	Simpson
3375	to	3435	Simpson - shale
3435	to	3452	Lime and sand
3452	to	3505	Lime
		3505	T. D.

Set 175' of 10" Surface pipe. Cemented with 100 sacks cement.
 Set 3315' of 7" O.D. casing. Cemented with 100 sacks cement.

<u>TOPS</u>	
Lansing	2018
Mississippi	2698
Hunton	3090
Viola	3243 to 55
Simpson	3373
Arbuckle	3452 (Derrick floor)

Perforated Lane wells 67 shots between 3241' and 3253'
 Temporary potential 284 barrels plus 15% water

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Van Ness #1, Section 20-14-2W, Saline County, Kansas, as reflected by files of the C. C. Nelson Drilling Company

RECEIVED
 STATE CORPORATION COMMISSION

MAY 8 1958

WARRANTY DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 20 T. 14 R. 20
 BOOK PAGE 99 LINE 4