


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-169-00787-00-00
WELL PLUGGING RECORD

Saline County, Sec. 20 Twp. 14 Rge. 2 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner West Supply Co., Inc.
Lease Name Van Ness #2 Well No. _____
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 5-7-58 19____
Application for plugging approved 5-10-58 19____
Plugging commenced 5-12-58 19____
Plugging completed 5-16-58 19____
Reason for abandonment of well or producing formation Depletion



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3249 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	180'	none
				5-1/2"	3237'	2715'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 3249' and found it open.
Filled w/sand to 3228' and ran 5 sacks of cement, with dump bailer. Pulled 5 1/2" casing and cleared hole. Bailed hole to 180', set a 10' rock bridge and ran 15 sacks of cement. Mudded to 20', set a rock bridge and ran 5 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE,
_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 58

Thomas V. Duggin
Notary Public.



PLUGGING
FILE SEC. 20 T. 14 R. 14
BOOK PAGE 100 LINE 37

15-169-00787-00-00

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: C. C. Nelson Drilling Company
 FARM: Van Ness #2
 LOCATION: NW NW SW
 Section 20-14-2W
 Saline County, Kansas
 COMMENCED: March 31, 1945
 COMPLETED: May 7, 1945

0	to	177	Surface sand
177	to	210	Surface sand
210	to	410	Shale and shells
410	to	495	Shale and shells
495	to	7785	Sandy lime
785	to	1575	Shale and shells
1575	to	1630	Lime
1630	to	1750	Shale and lime
1750	to	1860	Lime
1860	to	1990	Shale and shells
1990	to	2020	Shale
2020	to	2520	Lime
2520	to	2676	Shale
2676	to	2712	Lime
2712	to	2748	Chat
2748	to	2875	Lime and chert
2875	to	2890	Chat
2890	to	3070	Shale
3070	to	3090	Chert and lime
3090	to	3175	Lime
3175	to	3237	Shale
3237	to	3249	Lime
		3249	T.D.

Set 180 feet of 8 3/4 inch surface pipe. Cemented with 90 sacks cement.

Set 3237 feet of 5 1/2 inch casing. Cemented with 60 sacks cement.

Potential 145 barrels.

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Van Ness #2, NW NW SW, Saline County, Kansas, Section 20-14-2W, as reflected by files of the C. C. Nelson Drilling Company.

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this _____ day of June, 1945.

RECEIVED
 CORPORATION COMMISSION
 MAY 8 1958
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 20 T. 14 R. 24
 BOOK PAGE 99 LINE 5