

15-169-00781-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Saline County. Sec. 19 Twp. 14S Rge. 2W (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW SW NW
Lease Owner West Supply Company
Lease Name Johnson Well No. 1
Office Address Box 506 - Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil well
Date well completed August 10 19 52
Application for plugging filed January 5 19 54
Application for plugging approved January 6 19 54
Plugging commenced March 16 19 54
Plugging completed March 21 19 54
Reason for abandonment of well or producing formation Ceased production

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production September 19 53
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee
Producing formation Depth to top Bottom Total Depth of Well 3209 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	125'	None
				5-1/2"	3201'	2604'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3209' to 3190' and ran 6 sacks of cement. Mudded hole to 126', set a 10' rock bridge and ran 15 sacks of cement at 115'. Mudded hole to 25' and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
E. E. O'Brien (Employee of Owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. O'Brien
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of March, 1954

Edward E. O'Brien

Notary Public.



PLUGGING
FILE SEC 19 T 14 R 2W
BOOK PAGE 6 LINE 4

24-7968-S

3-53-20M

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1954
03-30-54
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-169-00781-00-00


Company- NORTHWESTERN DRILG. CO., INC.
 Farm- Johnson No. 1

SEC. 19 T. 14 R. 2W
 NW SW NW

Total Depth. 3209
 Comm. 7-25-52 Comp. 8-10-52

County Saline
 KANSAS

Shot or Treated.
 Contractor. Northwestern Drilg. Co., Inc.
 Issued. 6-7-52



CASING:

5 1/2" 3201' - 80 rot
 8 1/2" - 125'

Elevation. 1226

Production. Pmp. 60 BO & 10 BW

Figures Indicate Bottom of Formations.

surface	75
sand	98
anhydrite	600
lime	765
red beds	790
shale & lime	835
shale	1090
shale & lime	2735
lime wht broken	2766
shale	2770
cherty lime	2830
shale & lime	3155
chert & shale	3202
oil showing	
chert & shale	3209
Total Depth	

C rot 3190
15 - 125
5 - Top

Scout Tops:	
Lansing	1999
Kansas City	2141
Miss.	2628
Hunton	3040
Viola	3202
	(976)

PLUGGING
 FILE SEC 19 T 14 R 2W
 BOOK PAGE 6 LINE 4

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 30 1954
 CONSERVATION DIVISION
 Wichita, Kansas