

15-169-00771-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Saline County. Sec. 17 Twp. 14 Rge. 2W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SW SE NW

Lease Owner Frank J. Black
Lease Name Seitz #2 Well No. _____
Office Address McPherson, Kansas 67460
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5/13/77 _____ 19____
Plugging completed 5/18/77 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3253
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	148	none
				5 1/2"	3238	2557'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Checked hole, found bridge at 275', drilled bridge down to bottom. Ran sand to 3200' and
set 5 sacks cement. Shut pipe at 2560', pulled 81 joints. Set rock bridge at 220' and
4 yards ready mix.

PLUGGING COMPLETE.

MAY 23 1977

STATE CORPORATION COMMISSION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING
CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE, ss.
WALTER VOTH (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 77

My commission expires _____



Margaret Melcher
Notary Public.

June 23, 1946
JUN 28 1946

15-169-00771-00-00

COMPANY: Westgate-Greenland Oil Company
 CONTRACTOR: C. C. Nelson Drilling Company
 FARM: Seitz #2
 LOCATION: SW SE NW Section 17-14-2W
 Saline County, Kansas
 COMMENCED: May 14, 1946
 COMPLETED: June 1, 1946

9 at 454

0	to	70	Surface
70	to	150	Surface
150	to	240	Anhydrate and shale
240	to	275	Shale and shells
275	to	350	Anhydrate
350	to	445	Sandy lime and shale
445	to	520	Sandy lime
520	to	555	Shale and lime
555	to	680	Sand and lime
680	to	825	Lime and shale
825	to	1140	Shale
1140	to	1455	Shale and shells
1455	to	1545	Shale
1545	to	1695	Lime and shale
1695	to	1800	Shale and shells
1800	to	1945	Lime
1945	to	2075	Shale and lime
2075	to	2455	Lime
2455	to	2510	Lime and shale
2510	to	2670	Shale
2670	to	2719	Lime and chert
2719	to	2833	Chat
2833	to	2863	Lime and chert
2863	to	2912	Lime
2912	to	3035	Shale
3035	to	3114	Lime
3114	to	3194	Lime and shale
3194	to	3238	Shale
3238	to	3243	Viola Lime
		3243	T.D. Rotary
3243	to	3253	Viola Lime
		3253	T.D.

APR 30 1947
L. H. WICKS, S. S.

Set 148 feet of 8 5/8 inch surface pipe. Cemented with 100 sacks of cement.
 Set 3238 feet of 5 inch casing. Cemented with 50 sacks cement.

Top Lansing 2015. Top Hunton 3040.
 Mississippi Chat 2675. Top Viola 3238.
 3238 to 3243 Viola--oil stain.
 3243 to 3253 Viola--no show of oil.
 Acidized with 1000 gallons acid.
 STATE POTENTIAL 454 barrels.

C E R T I F I C A T E

I, C. C. Nelson, do hereby certify that the above and foregoing is a true and correct copy of log of the Seitz #2, Sec. 17-14-2W, Saline County, Kansas, as reflected by the files of the Nelson Drilling Company.

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 4th day of June 1946.

C. C. Nelson

Ester Russell

My commission expires *Mar 25, 1949*