

15-169-30000-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Locate well correctly on above
Section Plat

Saline County, Sec. 9 Twp. 14 Rge. 2 (E) (W)
 Location as "NE/CNWSW" or footage from lines NW SW
 Lease Owner Raymond Oil Co., Inc.
 Lease Name Graham #1 Well No.
 Office Address Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed 19
 Application for plugging filed 19
 Application for plugging approved 19
 Plugging commenced 8/26/74 19
 Plugging completed 8/30/74 19
 Reason for abandonment of well or producing formation depleted.
 If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was com-
 menced? yes

Name of Conservation Agent who supervised plugging of this well Toman
 Producing formation Depth to top Bottom Total Depth of Well 3176 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	205	none
				4 1/2"	3173'	2591' ✓

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 3125', ran 4 sacks cement. Loaded hole, shot pipe at 2880', spotted 25 barrels oil. Worked pipe, shot pipe at 2685', 2595', pulled 79 joints. Bailed hole to 200', ran 3 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 11 1974
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor VOTH CASING PULLING
 Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
 WLATER VOTH ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
 Chase, Kansas

Subscribed and Sworn to before me this 31st day of August 1974

MARGARET MELCHER
 NOTARY PUBLIC
 Rice County, Kansas
 My Commission Expires
 Feb. 15, 1975

Margaret Melcher
 Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock,
 Wichita, Kansas

15-169-30000-00-00

SEC. 9


T. 14
 C NW SW

R. 2N

Company: DONALD T. INGLING
 Farm: Graham No. 1

Total Depth. 3176'
 Comm. 5-6-64 Comp. 5-16-64
 Shot or Treated.
 Contractor. DONALD T. INGLING
 Issued. 2-13-65

County Saline
 KANSAS



Elevation. 1232' RB

Production. 10 BOPD 50 % WTR

8 5/8" 205' cem w/ 140 sx
 4 1/2" 3173' cem w/ 50 sx

Figures indicate Bottom of Formations.

clay & shale	40
10 to 16" streak of sand & shale	205
lime	390
shale & lime	820
lime & shale	1150
shale & shells	1510
lime & shale	1665
lime & shale streaks	1875
shale & lime streaks	2035
lime & shale	2145
lime	2670
lime & shale	2770
Mississippi	2930
lime & shale	3030
shale	3085
lime	3088
Hunton	3150
Maquoketa	3172
shale-Maquoketa	3176
Dolomite-Maquoketa	
Total Depth	

TOPS: SMP	2624
Mississippi	2840
Kinderhook	2980
Hunton	3088
Maquoketa shale	3172
Maquoketa Dolomite	

RECEIVED
 STATE CORPORATION COMMISSION

AUG 23 1974

CONSERVATION DIVISION
 Wichita, Kansas