

15-169-30009-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Saline County, Sec. 9 Twp. 14 Rge. 2 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SE
Lease Owner Walter J. Nelson
Lease Name Cravens JOKC Well No. 2
Office Address Salina, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 12-1-65 19____
Plugging completed 12-3-65 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3170 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	124'	None
				5-1/2"	3168'	2534'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to top of cement @ 2650', bottom plug previously set. Pulled 5 1/2" casing, bailed hole to 160', set rock bridge to 150' and dumped 25 sacks of cement @ 150'. Mudded hole to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1966

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas
(Address)



SUBSCRIBED AND SWORN TO before me this 11th day of December, 19 65.
Milton J. Volin
Notary Public.
My commission expires May 20, 1968

Conserved to state 5-13-5

15-169-30009-00-00

ROTARY DRILLING LOG

OWNER: Walter J. Nelson
Contr: Ja-Le Contracting Inc.
Lease: Cravens #2
Loc: Sw Se 9-14-2w

Casing: Set 8 5/8" casing
124' #85 sks cement
Set 5 1/2" oil string
@ 3168'

0 - 30	soil
30 - 60	sand
60 - 90	sand & shale
90 - 110	lime
110 - 124	lime
124 - 262	lime & shale
262 - 571	lime & shale
571 - 821	lime & shale
821 - 1282	lime & shale
1282 - 1600	shale w/lime streaks
1600 - 1890	shale w/lime streaks
1890 - 2014	lime & shale
2014 - 2124	lime & shale
2124 - 2235	lime & shale
2235 - 2365	lime & shale
2365 - 2445	lime & shale
2445 - 2605	lime & shale
2605 - 2626	lime, shale & chert
2626 - 2703	chert, w/shale streaks
2703 - 2747	chert, lime & shale
2747 - 2810	chert, lime & shale
2810 - 2860	lime & shale
2860 - 2880	lime & shale
2880 - 3022	lime & shale
3022 - 3060	lime & shale
3060 - 3170	lime, shale & dolomite

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1965
CONSERVATION DIVISION
Wichita, Kansas

Formation tops

anhydrite	90
fort riley	110
mississippi	2620
hunton	2986
maqoketa	3167