

15-169-30008-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Saline County, Sec. 9 Twp. 14 Rge. 2 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW SE S E SW JOKCC

Lease Owner Walter J. Nelson

Lease Name Craven Well No. 1

Office Address Salina, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__


Plugging commenced 2-23-66 _____ 19__

Plugging completed 2-25-66 _____ 19__

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3163 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	140'	None
				5-1/2"	3165 1/2'	2656

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3163', sanded hole to 3150' and dumped 5 sacks of cement @ 3150' with dump bailer. Pulled 5 1/2" casing, bailed fluid to 165', set rock bridge to 150' and ran 2 1/2 yards of ready-mix cement to cap well.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

MAR 4 1966

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~CONSULTANT~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of March, 1966

Milton J. Volin
Notary Public.

My commission expires May 20, 1968

15-169-30008-00-00

ROTARY DRILLING LOG

OWNER: Walter J. Nelson
Contr: Ja-Le Contracting Inc.
Lease: Cravens #1
Loc: ~~SW SE 9-14-2W~~
SESV 50 KCC

Casing: Set 85/8" surface casing @ 140' w/ 85 sks cement
Set 5 1/2" oil string @ 3165 1/2'

0 - 50	Soil
50 - 70	sand
70 - 96	sand & shells
96 - 114	lime
114 - 124	lime
124 - 262	lime & shale
262 - 470	lime & shale
470 - 700	lime & shale
700 - 910	lime & shale
910 - 1110	shale w/ lime streaks
1110 - 1338	shale w/ lime streaks
1338 - 1505	shale w lime streaks
1505 - 1795	shale w/ lime streaks
1795 - 1987	lime & shale
1987 - 2160	lime & shale
2160 - 2252	lime & shale
2252 - 2395	lime & shale
2395 - 2541	lime & shale
2541 - 2650	lime & shale
2650 - 2745	lime & chert
2745 - 2785	chert
2785 - 2890	shale, lime & chert
2890 - 3022	lime & shale
3022 - 3043	lime & shale
3043 - 3150	lime & shale
3150 - 3167	lime & dolomite

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1966

CONSERVATION DIVISION
Wichita, Kansas

formation tops

anahydrate	96
fort riley	114
mississippi	2740
hunter	2990
maquoketa	3163