



15-169-00767-00-00

COMPANY: Westgate-Greenland Oil Company  
 CONTRACTOR: Nelson Drilling Company  
 FARM: Vanier #1  
 LOCATION: SE SW NW of 8-14-2, Saline County, Kansas  
 COMMENCED: December 9, 1946  
 COMPLETED: January 3, 1947

0	to	28	Surface clay
28	to	63	Sand
63	to	105	Shale and shells
105	to	115	Sand
115	to	145	Shale and shells
145	to	158	Lime
158	to	245	Lime
245	to	258	Anhydrite
258	to	280	Lime and shale
280	to	385	Lime
385	to	500	Shale and sandy lime
500	to	515	Sandy lime
515	to	595	Lime and shale
595	to	735	Lime
735	to	820	Sandy lime
820	to	1555	Shale and shells
1555	to	1675	Lime and shale
1675	to	1750	Shale and shells
1750	to	1785	Lime
1785	to	1870	Lime and shale
1870	to	2035	Shale and lime shells
2035	to	2140	Lime and shale
2140	to	2270	Lime
2270	to	2555	Lime and shale
2555	to	2630	Shale
2630	to	2730	Miss. Chat
2730	to	2815	Chat
2815	to	2930	Lime
2930	to	3000	Shale
3000	to	3062	Lime
3062	to	3145	Lime and shale
3145	to	3184	Shale
3184	to	3324	Lime
3324	to	3346	Sandy Lime
3346	to	3380	Lime
3380	to	3402	Arbuckle
		3402	T. D. Rotary

Set 3240 ft. of 5 1/2 inch casing. Cemented with 100 sacks cement.  
 Set 158 ft. of 8 5/8 inch surface pipe. Cemented with 100 sacks cement.  
 Plug back to 3212 T.D.  
 Perforated well with 69 shots from 3182 to 3196. Acidized with 1000 gal. acid. Show oil and 6 Barrel water per hour.

Tops- Lansing 1950. Mississippi 2621. Hunton 2986. Viola 3184.  
 Simpson 3319. Arbuckle 3392-3400.

FILE 8 14 2W  
 BOOK SAC-94-44

