

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-169-00079-00-00
API NUMBER N/A

LEASE NAME Cusick

WELL NUMBER #1

SPOT LOCATION SW NE NE

SEC. 8 TWP. 14 RGE. 2 W

COUNTY Saline

Date Well Completed 12-3-61

Plugging Commenced 4-17-84

Plugging Completed 4-17-84

LEASE OPERATOR Okmar Oil Company
ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

PHONE #(316) 265-3311 OPERATORS LICENSE NO. 5245

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #5 in Salina, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Maquoketa Depth to top 3158' bottom 3162' T.D. 3162'

Dolomite
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Water	2610	32			
Hunton Lime	Water	2965	80	8 5/8	202	0
Maquoketa Dol.	Oil	3158	62	4 1/2	3160	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Mud from 3162' to 2100'.

20 sx 50/50 pozmix cmt from 2100' to 1819'.
Mud from 1819' to 295'. 55 sx 50/50 pozmix w/ 4% gel and 1% CaCl2 from 295' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jet Well Servicing License No. 6535
Address Box 534, Russell, KS 67665


STATE OF Kansas COUNTY OF Sedgwick, ss.

David W. Munro (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) David W. Munro

(Address) 970 Fourth Financial Center
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 84



RECEIVED
STATE CORPORATION COMMISSION

Cecelia A. Bowser
Notary Public

My Commission expires: August 5, 1987

MAY 02 1984
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4 1-84
Revised 06-83

WELL LOG - CUSICK NO. 1

15-169-00079-00-00

Donald T. Ingling et al, Lease Owner

Section 8-14-2W

Donald T. Ingling, Contractor

Location: SW NE NE

Commenced: 11-25-61

County: Saline

Completed: 12-3-61

Production:

Total Depth: 3162' (rotary)

Elevation: 1207 RB

Casing: 8 5/8" 202' (140 sacks cement)
4 1/2" 3160' (40 sacks cement)

Figures below indicate bottom formation

35 surface clay
75 sand and shale
125 shale
202 lime
300 lime
450 lime
645 lime
910 lime
1270 shale and shells
1395 shale and shells
1560 lime
1735 lime
1950 shale and lime
2090 lime
2200 lime
2335 lime and shale
2515 lime and shale
2610 shale
2657 Mississippi
2755 lime
2806 Mississippi
2915 shale
2990 shale
3020 lime
3067 lime
3105 shale
3162 shale
3162 Total Depth

I certify this is a true and correct copy of the above mentioned well.

STATE OF KANSAS, COUNTY OF SEDGWICK: ss.

Donald T. Ingling

Subscribed and sworn to before me, a Notary Public, in said county and state.

RECEIVED
STATE CORPORATION COMMISSION
Notary Public

ME Black

My commission expires: Feb. 27, 1964

FEB 28 1964

CONSERVATION DIVISION
Wichita, Kansas