


15-169-00766-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Russell County. Sec. 7 Twp. 14 Rge. 2 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines N $\frac{1}{2}$ S E $\frac{1}{2}$  NE $\frac{1}{4}$   
Lease Owner Sidey Oil Company  
Lease Name Sidey Oil Company Dillingham Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced March 23 19 53  
Plugging completed March 30, 19 53  
Reason for abandonment of well or producing formation  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkey  
Producing formation Depth to top Bottom Total Depth of Well 3166 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3166 feet to Surface feet for each plug set.

Hole filled with sand from 3166 feet to 3155 feet; Six sacks of cement placed in hole with dump bailer to form cement plug from 3155 feet to 3107 feet; casing pulled and sixty six barrels of mud pumped in hole with Halliburton pump truck, filling hole with mud to 152 feet; fifteen sacks of cement pumped in hole, with wooden plug above cement; wooden plug forced down to 107 feet; five additional sacks of cement placed above wooden plug, forming cement plug between wooden plug at 107 feet and 90 feet; hole filled with mud with pump truck to 17 feet. Hole capped with five sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 9 - 1953  
04-09-53  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Barnes and Sons Pipe Pulling Co  
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
V. D. Sidey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *V. D. Sidey*  
P. O. Box 387, Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 8th day of April, 1953

My commission expires Jan. 31, 1957

*Seward S. Greider*  
Notary Public.

My commission expires ~~Sept. 27, 1956~~

PLUGGING  
FILE SEC 7 T 14 R 2W  
BOOK PAGE 85 LINE 41

15-169-00766-00-00

# SIDEY DRILLING COMPANY

BUILDING & LOAN BLDG.

P. O. BOX 387

RUSSELL, KANSAS

COMPANY V. D. Sidey Oil Company

SEC. 7 T. 14 R. 2  
LOC. 60A S $\frac{1}{2}$  NE $\frac{1}{4}$

FARM Dillingham NO. 1

TOTAL DEPTH 3166'  
COMM. 1-28-52  
SHOT OR TREATED  
CONTRACTOR Sidey Drilling Company  
ISSUED

COUNTY Saline

CASING  
20 10  
15 $\frac{1}{2}$  8 $\frac{1}{2}$  164'  
12 $\frac{1}{2}$  6 $\frac{1}{2}$   
13 $\frac{1}{2}$  5 5/16 3183.20'

ELEVATION 1212 DF  
1210 GR  
PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-30	Shale	2195-2270	Lime
30-65	Sand	2270-2360	Lime and Shale
65-95	Shale	2360-2440	Lime and Shale
95-100	Sand	2440-2520	Lime and Shale
100-142	Shale and Shells	2520-2570	Shale and Lime
142-154	Anhydrite	2570-2635	Shale and Lime
154-310	Broken Lime	2635-2675	Lime
310-340	Red Rock	2675-2750	Lime
340-370	Broken Lime	2750-2780	Lime
370-545	Broken Lime	2780-2815	Lime
545-635	Broken Lime	2815-2875	Shale and Lime
635-740	Broken Lime	2875-2945	Lime and Shale
740-800	Lime and Shale	2945-2973	Shale
800-1060	Shale and Shells	2973-3105	Lime
1060-1335	Shale and shells	3105-3163	Shale
1335-1550	Shale and Shells	3163-3166	Lime TD
1550-1700	Shale and Lime		
1700-1855	Shale and Lime		
1855-1960	Lime and Shale		
1960-2040	Lime		
2040-2110	Lime		
2110-2195	Lime and Shale		

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 21 1953  
CONCESSION DIVISION

STATE OF KANSAS, COUNTY OF RUSSELL s.s.

I, V. D. Sidey, of the Sidey Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Dillingham # 1 well.

*V. D. Sidey*  
V. D. Sidey

Subscribed and sworn to before me this 8th day of October, 1952.

My Commission Expires: September 17, 1956

*Marguerite Byrne*  
Notary Public

PLUGGING  
FILE SEC 7 T 14 R 2 W  
BOOK PAGE 85 LINE 41