


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

15-169-00760-00-00

NORTH



Locate well correctly on above Section Plat

Saline

County, Sec. 7, Twp. 11, Rge. 2 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW NE

Lease Owner J.A. Davis-J.H. Child

Lease Name Dillingham Well No. 1

Office Address 121 W 2nd Hutchinson Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed 5-18-47 19

Application for plugging filed 6-4-51 19

Application for plugging approved 6-4-51 19

Plugging commenced 6-5-51 19

Plugging completed 6-15-51 19

Reason for abandonment of well or producing formation

Not economical to produce

If a producing well is abandoned, date of last production 6-1- 19 51

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel E. Durke

Producing formation Viola Depth to top 3177 Bottom 3178 Total Depth of Well 3178 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 3177', 5 1/2" csg. @ 3175', 8 5/8" csg. @ 156'
Run 5-sks. cement from 3177' to 3145'
Fill with mud to 160' & with rock to 155'
Run 15-sks. cement from 155' to 110'
Fill with mud from 110' to 15'
Cap with 5-sks. cement from 15' to 10'
Pull 2511' of 5 1/2" csg., 8 5/8" csg. left in (cemented)
Work started 6-5-51, complete 6-15-51.

REC
STATE CORP

JUL 20 1951 07-20-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J.A. Davis-J.H. Child
Address 121 West 2nd Street--Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

_____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J.H. Child for J.A. Davis-J.H. Child*

121 W 2nd Hutchinson Ks.


(Address)

SUBSCRIBED AND SWORN to before me this 18 day of July, 19 51

8/30/52

June Deming
Notary Public.

My commission expires



STERLING DRILLING CO.
STERLING, KANSAS

15-169-00760-00-00

WELL LOG -----DILLINGHAM #1

Location -- Within 100' of the center of the West 20 Acres known as Tract 6 in the amended plat of the Farm Sub-division of the Thomas White Farm in the Northeast 1/4 of Section 7, Township 14, Range 2W, Saline County, Kansas.

Owners -- J. A. Davis & J. H. Child, et al
Contractor-- Sterling Drilling Company, Sterling, Kansas

Date Commenced -- April 18th, 1947
Date Completed -- April 30th, 1947 w/r
May 8th, 1947 c/t

Total Depth -- 3178' w/r

CASING RECORD

156' 8" Surface Casing
Cemented with 145 Sacks Cement

3159' 5 1/2" Production Casing
Cemented with 75 Sacks Cement

LOG

0- 40	Surface Clay
40- 100	Sand
100- 155	Shale
155- 675	Lime
675- 730	Shale
730- 890	Lime & Shale
890-1580	Shale & Shells
1580-1930	Lime
1930-1970	Shale
1907-2120	Lime
2120-2240	Lime & Shale
2240-2445	Lime
2445-2615	Broken Lime
2615-2730	Lime
2730-2775	Miss. Dolomite
2775-2835	Lime
2835-2975	Shale
2974-3109	Lime
3109-3177	Shale
3177-3178	Viola

Total Depth 3178' w/r

PRODUCTION

Producer.