

15-169-00401-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Saline County, Sec. 7 Twp. 14 Rge. 2W (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines. SE SW SW
Lease Owner Raymond Oil Co., Inc.
Lease Name Jarvis #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19__
Application for plugging filed 19__
Application for plugging approved 19__
Plugging commenced 3/6/73 19__
Plugging completed 3/12/73 19__
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3187 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	152	none
				5 1/2"	3185 1/2	2461'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3170' and dumped 5 sacks cement.
Shot pipe at 2700', 2605', 2500', pulled 77 joints. Allied pumped 3 sacks hulls, 20 sacks gel and 90 sacks cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1973

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 13th day of March, 1973

My commission expires

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975



Margaret Melcher
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15-169-00401-00-00

Company- DON MCKELLAR
Farm- Jarvis No. 1

SEC. 7 T. 14 R. 2W
SE SW SW

Total Depth. 3187'
Comm. 12-28-61 Comp. 1-4-62
Shot or Treated.
Contractor. Blackstone Drig., Inc.
Issued. 5-12-62

County Saline KANSAS



CASING:

8 5/8" 152.50' cem w/130 sx.
5 1/2" 3185.50' cem w/70 sx.

Elevation. 1213' RB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

sand	55
shale & shells	151
lime	850
shale & shells	1585
shale & lime	2010
lime	2050
shale & lime	2626
Mississippi	2685
lime & chert	2810
lime & shale	2861
shale	3000
Hunton Lime	3103
Maquoketa Shale	3185
Maquoketa Dolomite	3187
Total Depth	

TOPS: SCOUT	
Mississippi	2626
Kinderhook	2867
Hunton	3000
Maquoketa Shale	3103
Maquoketa Dolomite	3185

2685
1213
1472

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1963
CONSERVATION DIVISION
Wichita, Kansas