

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15,171-20372-01-00

LEASE NAME Newcomer

WELL NUMBER #1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 24 TWP. 17 RGE. 31 (E) or (W)

COUNTY Scott

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-27-88

Plugging Completed 11-1-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Chief Drilling Co., Inc.

ADDRESS 151 N. Main Suite 700, Wichita, Ks. 67202

PHONE (316) 653-4856 OPERATORS LICENSE NO. 5886

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 31, 1988 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filled? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER PRODUCTION RECORDS

CASING RECORD

Formation	Contents	From	To	Size	Put In	Pulled out
	<u>NOV 7 1988</u>			<u>8-5/8"</u>	<u>263'</u>	<u>None</u>
				<u>4-1/2"</u>	<u>4587'</u>	<u>581.40'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4220' and 4 sacks cement. Shot casing at 3000', 2500' and 1350'. Allied squeezed well with 5 sacks gel and 50 sacks 60/40 pozmix cement with 6% gel displaced to 1300'. Shot casing at 600' spotted 50 sacks cement, pulled casing to 275', spotted 40 sacks cement, pulled casing to 40', pumped 10 sacks cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chief Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1988

Iona M. Leatherman  
Notary Public

My Commission Expires \_\_\_\_\_

