

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-171-00081-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Scott

County. Sec. 35 Twp. 17S Rge. (E) 32 (W)

NORTH

		#1

Locate well correctly on above
Section Plat

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE $\frac{1}{4}$ of NE $\frac{1}{4}$ of NE $\frac{1}{4}$
Lease Owner Amerada Pet. Corps
Lease Name Core Crowell Well No. 1
Office Address Box 2040, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Feb. 17, 1951
Application for plugging filed Feb. 17, 1951
Application for plugging approved Feb. 17, 1951
Plugging commenced Feb. 18, 1951
Plugging completed Feb. 18, 1951
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough of Great Bend, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5354' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8" OD	281'	None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud up to 281' down from top. Set Halliburton Plug at 281' down from top. Mixed & poured in 20 sacks regular cement through 4 1/2" drill pipe, filled up to 219' down from top, filled hole with heavy mud to within 30' of top of surface casing in bottom of cellar, set Halliburton Plug, mixed & dumped in 10 sacks of regular cement filling hole to top of surface casing in bottom of cellar. Well Plugged & abandoned 2/18/51 as per requirements of State Plugger Mr. C. D. Stough of Great Bend, Kansas.

RECEIVED
STATE CORPORATION COMMISSION
MAR - 8 1951
CONSERVATION DIVISION
Wichita, Kansas
03-05-1951

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Amerada Pet. Corps
Address Box 2040
Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
C. N. Rose (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) C. N. Rose

SUBSCRIBED AND SWORN TO before me this 26 day of February, 1951

My commission expires January 17, 1955 Notary Public.

23-5091-s 8-50-10M

PLUGGING
FILE SEC 55 T 17 R 32
BOOK PAGE 63 LINE 7

15-171-00081-00-00

Well No. 1
 Farm Cora Crowell
 Elevation 2970' Derrick Floor
 Location 330' South of North line
 330' West of East line of NE/4
 Section 35-17S-32W
 Scott County, Kansas
 Company Amerada Petroleum Corporation
 Commenced Drlg. 1-18-51
 Completed Drlg. 2-18-51
 Contractor Glenn W. Peel
 Initial Production: Dry Hole

<u>CASING RECORD:</u>	<u>SIZE</u>	<u>WEIGHT</u>	<u>FEET</u>	<u>CEMENT</u>	<u>PERFORATIONS</u>
	8-5/8"	24#	281'	200 Sx	None

FORMATION:

Surface	0	140	
Sand	140	170	
Shale	170	282	
Shale & Shells	282	720	
Shale	720	1510	
Shale & Shells	1510	1770	
Anhydrite	1770	1815	
Shale & Red Bed	1815	1920	
Shale	1920	2060	
Shale & Shells	2060	2265	
Shale & Salt	2265	2290	
Shale	2290	2450	
Shale & Lime	2450	2565	
Lime & Shale	2565	2850	
Lime	2850	3420	
Lime & Shale	3420	3950	
Lime	3950	4300	
Bentonite	4300	4310	
Lime	4310	4405	
Lime & Shale	4405	4460	
Lime	4460	4475	
Lime & Shale	4475	4530	
Lime	4530	4985	
Lime & Chert	4985	5033	
Lime	5033	5354	T.D.

GEOLOGICAL TOPS:

Lansing	3905'
Mississippi	4562'
Viola	5143'
Arbuckle	5189'

Rotary tools used from 0 5354'

PLUGGING
 FILE SEC 35 T 17 R 370
 BOOK PAGE 63 LINE 7

RECEIVED
 STATE CORPORATION COMMISSION
 MAR - 8 1951
 CONSERVATION DIVISION
 Wichita, Kansas
 03-08-1951