

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 South Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

API NUMBER 15-171-20509-00-00

LEASE NAME Erskin "A"

WELL NUMBER 1-28

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4950 Ft. from South Section Line

2310 Ft. from East Section Line

SEC 28 TWP 17S RGE 32 West

COUNTY Scott

Date Well Completed 4/3/1997

Plugging Commenced 3/5/2002

Plugging Completed 3/5/2002

LEASE OPERATOR Larson Operating Company  
A Division of Larson Engineering, Inc.

ADDRESS 562 West Highway 4 Olmitz, KS 67564-8561

PHONE # (316) 653-7368 OPERATORS LICENSE NO. 3842

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/20/2002 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Morrow Sand Depth to Top 4630' Bottom 4636' T.D. 4790'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Morrow Sand	oil & water	surface	430'	8-5/8"	430'	none
Pleasanton	water	surface	4784'	5-1/2"	4784'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

CIBP @ 4480', CIBP @ 4003', port collar @ 2320' cemented with 150 sx to surface  
Perforated base of Cedar Hills @ 2044'. Broke down perforations w/ 1800#. Took injection rate 3 bpm @ 800#. Cement down casing w/ 185 sx 60-40 poz w/ 6% gel & 300# hulls in first cement. Pressured to 1100#. SI w/ 1100#. Pressured braidenhead to 500# - held. Plugging complete at 10:00 am, 3-5-02.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Swift Services, Inc. License No. 32382

Address P.O. Box 466, Ness City, KS 67560-0466

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Larson Operating Company

STATE OF KANSAS COUNTY OF BARTON, ss.

Thomas Larson (Employee of Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Thomas Larson

(Address) 562 West Highway 4 Olmitz, KS 67564-8561

SUBSCRIBED AND SWORN TO before me this 6th day of March, 20 02

Carol S. Larson  
Carol S. Larson Notary Public

My Commission Expires: June 25, 2005



OR