

15-171-20073-00-00

FORM CP-4


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Scott County, Sec. 24 Twp. 17S Rgn. 32W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW SE
Lease Owner Beren Corporation OK user
Lease Name Stegman Well No. 1
Office Address 1130 Vickers-KSB&T Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed December 20 19 74
Application for plugging filed December 20 19 74
Application for plugging approved December 20 19 74
Plugging commenced December 20 19 74
Plugging completed December 20 19 74
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W.L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4050' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	332'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud up to 975'. Cemented with 70 sx. 50-50 pozmix, 6% gel. Filled hole up to 240' & cemented with 20 sx. 50-50 pozmix, 6% gel. Set plug @ 40' w/ 1/2 sk. hulls & 10 sx. cmt. 2 sx. in rathole.

RECEIVED
STATE CORPORATION COMMISSION

MAR 7 1975

03-01-1975

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Linda H. Dickens


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of December, 19 74

My commission expires December 28, 1977

D'Ann Drennan
Notary Public.



15-171-20073-00-00

DRILLERS LOG

No. 1 Stegman

CASING RECORD:

8-5/8" @ 332'
w/225 sx. cmt.

COMPANY:

Beren Corporation

DESCRIPTION:

C NW SE
24-175-32W
Scott County,
Kansas

CONTRACTOR:

Red Tiger Drilling Co.

COMMENCED:

December 13, 1974

COMPLETED:

December 20, 1974

TOTAL DEPTH: 4050'

ELEVATION:

FORMATION

FROM

TO

REMARKS

Shale & Sand	0	239
Shale	239	335
Shale & Sand	335	742
Shale	742	1523
Shale & Redbed	1523	1794
B. Anhydrite	1794	1829
Shale & Redbed	1829	1888
Redbed & Shale	1888	1900
Sand	1900	2057
Shale & Redbed	2057	2257
Anhydrite	2257	2264
Shale	2264	2299
Anhydrite	2299	2318
Redbed	2318	2456
Redbed & Shale	2456	2530
Shale w/Lime	2530	3758
Lime w/Shale	3758	3899
Lime	3899	4050

RECEIVED
STATE CORPORATION COMMISSION

MAR 7 1975
03-07-1975
CONSERVATION DIVISION
Nichte: 46323

MILLERS FALLS

ONION SKIN

COTTON CONTENT

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens

Linda H. Dickens

Subscribed and sworn to before me this 26th day of December, 1974.

D'Ann Doremans
Notary Public

My Commission Expires:

December 28, 1977

