


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above Section Plot

Scott County, Sec. 20 Twp. 17 Rge. 32 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SW 1/4
Lease Owner Car-Ren Inc.
Lease Name Sprier Well No. 1-20
Office Address 645 Garvey Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Gas
Date Well completed _____ 19____
Application for plugging filed Jan. 10 1977
Application for plugging approved Jan. 11 1977
Plugging commenced Jan. 10, 1977
Plugging completed Jan. 12 1977
Reason for abandonment of well or producing formation _____
Non Comercial value.
If a producing well is abandoned, date of last production _____
None 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Balthazor
Producing formation Hugoton Depth to top 2822 Bottom 2829 Total Depth of Well 2925
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0'	356'	8 5/8"	356'	0'
Hugoton		0'	2924'	4 1/2"	2924'	2144'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pump 1 sack hulls & 10 sacks cement to 2675'-Pressured to 750lbs.
Mud 2675' to 1000'
Pumped 25 sacks cement 1000' to 920'
Mud 920' to 350'
Pumped 25 sacks cement 350' to 280'
Mud 280' to 40'
Put bridge & 10 sacks cement 40' to 0'
Cut off 8 5/8" 42" below ground level

Rec'd
01-23-1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling
Box F, Sublette, Kansas 67877 Ks. Permit #766

STATE OF Kansas COUNTY OF Haskell, ss.
I Edgar J. Eves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
Box F, Sublette, Kansas 67877
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of January, 1977

Louisa L. Eves
Notary Public.

My commission expires Dec 6, 1980



15-171-20108-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Sprier #1-20
C-SW/4 Sec 20-17S-32W
Scott County Kansas

Commenced: 11-6-76

Completed: 11-12-76

OPERATOR: CAR-REN, INC.

Depth		Formation	Remarks
From	to		
0	360	Surface Clay-Sand-Shale	Ran 9 jts of used 8 5/8" csg set @ 356'
360	2545	Shale	
2545	2645	Lime-Shale	Cemented w/265 sks Common
2645	2800	Shale-Lime	2% Gel - 3% CC - 1/2# Floseal
2800	2925	Lime-Shale	PD @ 7:30 p.m. 11-6-76
	2925 - TD		Ran 71 jts of 9 1/2" 4 1/2" csg set @ 2925' Cemented w/ 175 sks 50/50 Posmix 10% Salt 3/4 of 1% CFR-2 PD @ 5:00 a.m. 11-12-76

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 19th day of November, 1976.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY

My Commission expires February 6, 1979.



RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1977
01-10-1977
CONSERVATION DIVISION
Wichita, Kansas