

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-30002-000

LEASE NAME Smith #1-35

WELL NUMBER _____

SPOT LOCATION C SW

SEC. 35 TWP. 19S RGE. 33W (E) or

COUNTY Scott

Date Well Completed _____

Plugging Commenced 3/5/84

Plugging Completed 5/17/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cargill Natural Gas Operations bought by Kelso
ADDRESS 604 One Main Place, Wichita, Ks. 67202 Casing Pulling

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 2655'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8.5/8	291'	none
				5"	2654	1022

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 2580' & ran 5 sacks cement, shot pipe at 1917', 1712', 1511', 1406', 1319', 1212', 1104', & 1022'. Pulled 33 joints of pipe. Plugged well with 2 hulls, 10 gal. 50 cement, 10 gal. 1 hull, plug, & 225 sacks 50/50 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1984

IRENE HOOVER
State of Kansas
My Comm. Exp. Aug. 15, 1985

Notary Public

My Commission expires.

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1984

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-171-30002-00-00

Copy

Company- SATURN OIL & GAS
Farm- Smith No. 1

SEC. 35 T. 19 R33W
CSW

Total Depth. 2657
Comm. 12-31-64 Comp. 1-4-65
Shot or Treated.
Contractor. Earl Wakefield
Issued. 6-19-65

County Scott KANSAS

CASING:
3 5/8" @ 291'
4 1/2" @ 2654'

Elevation. 2965' KD

Production. 2060 MCFGPD

Figures indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE

Top of blue shale 134
Base of Cimarron Anhydrite 2192

K. G. S. LIBRARY

TOPS: Log

Herrington 2601
Kridler 2630

2634-42' Dolomite, light tan, fine to crystalline black fossiliferous mottled, good vuggy porosity.

2644-54' (RTD) Dolomite, as above with more black fossil inclusions.

LOGS RUN: Schlumberger ran Gamma-ray, Sonic, Caliper & Laterlog Surveys.