

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 5171-20,380-00-00

LEASE NAME Smith

WELL NUMBER #1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 35 TWP. 19 RGE. 33 (E) or (W)

COUNTY Scott

Date Well Completed 4-14-89

Plugging Commenced 8-15-89

Plugging Completed 8-15-89

LEASE OPERATOR Robert F. Hembree

ADDRESS P.O. Box 458 Ness City, Ks. 67560

PHONE# (913) 798-3408 OPERATORS LICENSE NO. 8247

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-14-89 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Pleasanton Depth to Top 4239 Bottom 4248 4387

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pull in
		Surface	388'	8 5/8	388'	-0-
		Surface	4387'	4 1/2	4387'	2,517

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Dumped 50' of sand over top of perforations (to 4189'), Dumped 4 sx of cement with dump bailer. Pulled 2517' of 4 1/2 casing from well. Allied Cementing mixed 400# hulls, 10 sx gel, 50 sx 60/40 6% gel, 10 sx gel 100# hulls and pumped down well to plug from 4189' to 388'. Released 8 5/8" wooden plug and pumped down surface pipe with 150 sx of 60/40 6% gel. Cement to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hembree Well Service Inc. License No. 6907

Address P.O. Box 458 Ness City, Ks. 67560

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert F. Hembree

STATE OF Kansas COUNTY OF Ness, ss.

Fred J. Hembree (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Fred J. Hembree

(Address) P.O. Box 458 Ness City, Ks. 67560

SUBSCRIBED AND SWORN TO before me this 7th day of Sept., 19 89

Colette S. Traxler  
Notary Public



My Commission Expires: 12-22-91