

15-171-20015-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Scott SEC. 35 TWP. 19S RGE. 33W  W  
Location as in quarters or footage from lines:  
510' FN & 660' FE NW/4


Lease Owner Maurice L. Brown Company - #6234  
Lease Name Smith Well No. 6 SWD  
Office Address 200 Sutton Place, Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): SWD  
Date Well Completed March, 1969  
Application for plugging filed 5-23-83  
Plugging commenced 7-19-83  
Plugging completed 7-19-83  
Reason for abandonment of well or producing formation Non Co-commercial Value

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Luthi

Producing formation SWD Depth to top 4089' bottom 4212' T.D. 4750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface				8 5/8"	372'	0'
Production	Wtr.	4089	4212	2 7/8"	4287	0'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Hole filled w/ sand to 1500'  
Pumped 1 sk. hulls & 28 sks. cement 1500' to 0'  
Pressured to 400 lbs.  
Cut off 8 5/8" & 2 7/8", 3' below ground level  
Fill 8 5/8" to ground level w/ 1 sk. cement

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 09 1983  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Midwest Casing Pulling Service  
Lic. #6497

STATE OF Kansas COUNTY OF Haskell, ss.  
I, Edgar J. Eves (~~employee or owner~~) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves  
Box F, Sublette, Ks. 67877  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 83

Sandra L Eves  
Notary Public.

My Commission expires: 12-6-84



