

API NUMBER 15-171-20,272-00-10

LEASE NAME Bontrager

WELL NUMBER 1-32

       Ft. from S Section Line

       Ft. from E Section Line

SEC. 32 TWP. 19 SRGE. 33 (N) (M) (W)

COUNTY Scott

Date Well Completed           

Plugging Commenced 12-13-95

Plugging Completed 12-15-95

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Lebsack Oil Production, Inc.

ADDRESS P.O. Box 489 Hays, Ks. 67601

PHONE (913) 625-5444 OPERATORS LICENSE NO. 5210

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on            (date)

by            (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached?           

Producing Formation            Depth to Top            Bottom            T.O. 4800

Show depth and thickness of all water, oil and gas formations.

RECEIVED  
 KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	420.5	none
				5-1/2"	4799'	2021'

DEC 21 1995  
 12-21-95

CONSERVATION DIVISION  
 WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from        feet to        feet each set Plugged off bottom with sand to 4118' and 5 sacks cement. Shot pipe at 2521' and at 2021' pulled to 800', pumped 80 sacks cement (60/40 6% gel) pulled to 450', pumped 50 sacks cement 60/40 6% gel. Circulated cement to surface and topped off with 30 sacks cement (60/40 6% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lebsack Oil Production, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 20th day of December, 19 95

Irene Herzberg  
 Notary Public

My Commission Expires:  
 USE ONLY ONE SIDE OF EACH FORM

