

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-171-20,403-0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR National Cooperative Refinery Ass OPERATOR'S LICENSE NO. 5565

ADDRESS 1775 Sherman St., Suite 3000, Denver, CO 80203 PHONE # (303) 861-4883

LEASE (FARM) Hattendorf WELL NO. 1 WELL LOCATION NE/4 COUNTY Scott

SEC. 34 TWP. 19S RGE. 34 (~~EX~~ (W) TOTAL DEPTH 5000' PLUG BACK TD _____

Check One:

OIL WELL ___ GAS WELL ___ D & A x SWD or INJ WELL ___ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 310.63' CEMENTED WITH 250 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD x POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 2300'-50 sx. 2nd

plug at 1470'-80 sx., 1 sack Flocel. 3rd plug at 810'-40 sx. 4th plug at 330'-40 sx. 5th

plug at 40'-10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No

(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 12:45 a.m. on 02-05-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Anthony Martin PHONE # (913) 743-5443

ADDRESS 533 N. Main, Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

FEB 9 1990
02-09-90
CONSERVATION DIVISION
Wichita, Kansas

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: 02-08-90