

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33406
Name: Garner, Thomas
Address 1: 305 E 7th
Address 2: _____
City: St John State: KS Zip: 67576 + 1652
Contact Person: Tom Garner
Phone: (620) 549-6618
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 145-01304-00-00
Spot Description: _____
SE SE SE Sec. 33 Twp. 22 S. R. 15 East West
330 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Pawnee
Lease Name: Fergus A Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: 10/15/11 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 12/15/11
Plugging Completed: 12/18/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	9.625	657	415 Sacks Cement
		Production	7.00	4058	85 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 75 sacks cement & 300# hulls; displaced to 3400'. Tagged cement at 3340'. Had Log-Tech shoot pipe off at 1080'. Pulled 7" casing out & ran 2 7/8" tubing to 990'. Pumped 20 gel & 80 sacks cement. Pulled to 540', ran 5 joints tubing in & pumped 80 sacks cement at 690'. Pulled to 310' & pumped 50 sacks cement. Pulled to 60' & pumped 35 sacks cement. Pulled rest of tubing out.

RECEIVED
JAN 06 2012
KCC WICHITA

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc
Address 1: 190 US Hwy 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3409

Name of Party Responsible for Plugging Fees: Garner, Thomas
State of Kansas County, Stafford, ss.
Thomas Garner
(Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: [Signature]