

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5004  
Name: Vincent Oil Corporation  
Address 1: 155 N. Market, Ste 700  
Address 2: \_\_\_\_\_  
City: Wichita State: KS Zip: 67202 + 1821  
Contact Person: M.L. Korphage  
Phone: (316) 262-3573  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 4565  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 047-21602-00-00  
Spot Description: W/2-W/2-SE  
W/2, W/2, SE Sec. 30 Twp. 26 S. R. 16  East  West  
1,320 Feet from  North /  South Line of Section  
2,245 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Edwards  
Lease Name: Thompson Well #: 8  
Date Well Completed: 12/17/2011  
The plugging proposal was approved on: 12/15/2012 (Date)  
by: Eric MacLaren, KCC Dist. I (KCC District Agent's Name)  
Plugging Commenced: 12/16/2011  
Plugging Completed: 12/17/2012

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface Casing	8 5/8"	479'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Loaded hole with heavy drilling mud and set cement plugs through drill pipe as follows:  
50 sx at 1110', 50 sx at 510', 30 sx at 270', 20 sx at 60' to surface; plugged rathole with 30 sx and mousehole with 20 sx. Used a total of 200 sx of 60 / 40 POZ (4% Gel & 1/4# Cel-flake/sx)

Plugging Contractor License #: 5929 Name: Duke Drilling Co. Inc.  
Address 1: P.O. Box 823 Address 2: \_\_\_\_\_  
City: Great Bend State: Kansas Zip: 67530  
Phone: (620) 793-8366  
Name of Party Responsible for Plugging Fees: Vincent Oil Corporation  
State of Kansas County, Sedgwick, ss.  
M.L. Korphage  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: M.L. Korphage

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JAN 12 2012

KCC WICHITA

AC

# QUALITY WELL SERVICE, INC.

5393

Home Office 324 Simpson St., Pratt, KS 67124

Todd's Cell 620-388-5422  
Office / Fax 620-672-3663

Rich's Cell 620-727-3409  
Brady's Cell 620-727-6964

Date	12-16-11	Sec.	30	Twp.	26	Range	16W	County	Edwards	State	KS	On Location		Finish	12:30
Lease	Thompson		Well No.	8		Location									
Contractor	Duke 2					Owner									
Type Job	PTA					To Quality Well Service, Inc.									
Hole Size	7 7/8					You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.									
Csg.						Depth					Charge To				
Tbg. Size						Depth					To Vincent Oil Corp				
Tool						Depth					Street				
Cement Left in Csg.						Shoe Joint					City				
Meas Line						Displace					State				
EQUIPMENT										The above was done to satisfaction and supervision of owner agent or contractor.					
Pumptrk	8	No.	Duc		Cement Amount Ordered										
Bulktrk	9	No.	Inced		200ss					60/40 4% Gel					
Bulktrk		No.			Common					120					
Pickup		No.			Poz. Mix					90					
JOB SERVICES & REMARKS										Gel.					
Rat Hole	30.52	60/40	4 Gel	1/4 CF	7										
Mouse Hole	30.52	60/40	4 Gel	1/4 CF	Calcium										
Centralizers	Hulls														
Baskets	Salt														
D/V or Port Collar	Flowseal 50														
	Kol-Seal														
	Mud CLR 48														
	CFL-117 or CD110 CAF 38														
	Sand														
1st Plug	1120'	50.52	60/40	4% Gel	1/4 CF	Handling 207									
2nd Plug	520'	50.52	60/40	4% Gel	1/4 CF	Mileage 30									
FLOAT EQUIPMENT															
3rd Plug	280'	30.52	60/40	4% Gel	1/4 CF	Guide Shoe									
4th Plug	60'	30.52	60/40	4% Gel	1/4 CF	Centralizer									
										Baskets					
										AFU Inserts					
										Float Shoe					
										Latch Down					
										1 - Wooden Plug					
										Pumptrk Charge PTA					
										Mileage 30					
										Tax					
										Discount					
										Total Charge					
Signature										1.470					

RECEIVED

JAN 12 2012

KCC WIC HTA