

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-035-22,248

LEASE NAME KLIEWER

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line
 C S E N E
 Ft. from E Section Line

LEASE OPERATOR RANGE OIL CO INC

SEC. 16 TWP. 33 RGE. 4 (E) of (W)

ADDRESS 1120 KSRAT BLDG. WICHITA KS

COUNTY COWLEY

PHONE # (316) 265-6221 OPERATORS LICENSE NO. 5120

Date Well Completed

Character of Well oil

Plugging Commenced 8/14/91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/17/91

The plugging proposal was approved on 8/14/91 (date)

by DIST # 2 (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation MISS. Depth to Top 3206 Bottom 3222 T.D. 3250

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8</u>	<u>217</u>	<u>0</u>
				<u>4 1/2</u>	<u>3249</u>	<u>2428</u>

AUG 22 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

FILLED WITH CHAT TO 32150 & DUMP 4 SK CEMENT
SHOT CASING LOOSE AT 2428 & LAYED DOWN.
SET ROCK BRIDGE AT 275' TO 250' & DUMP 5403 SLURRY MIX
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B2 S WELL SERVICE License No. 6013

Address PO Box 837 WINFIELD KS 67151

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RANGE OIL CO.

STATE OF KS COUNTY OF COWLEY, ss.

Bob Deuter (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Bob Deuter

(Address) WINFIELD KS

SUBSCRIBED AND SWORN TO before me this 19th day of August, 19 91

Wayneva C. Opperman
Notary Public

My Commission Expires: February 29, 1992

WELL COMPLETION REPORT AND DRILLER'S LOG

S. 16 T. 33S R. 4 E

Loc. C SE NE

County Cowley

API No. 15 - 035 - 22248 - 0000

Operator Range Oil Company, Inc.

Address 240 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Well No. 1 Lease Name Kliewer

Footage Locatio

Principal Centre

Spud Date

Directional Devi

Report of

Purpose of

Top, ft.

Size



Date of first pri

RATE OF PROD PER 24 HOURS

Disposition of g

INSTRUCTIC mitted to th. Division, Stat Rule 82-2-12

STATE KANSAS 8-3-70 MAP NO. S-T-R 16-33S-4E D
OPER RANGE OIL CO INC SPOT C SE NE INIT
240 PAGE COURT, WICHITA, KS 67202 CO COWLEY DO
WELL 1 KIEWER ELEV 1210 KB FIN
CONTR OWN
FIELD POSEY NE (MISS)
IPP 5 BOPD + WTR (MISS) 3206-22 OA
API 15-035-22248 FR 5-31-79



SPUD 5-31-79, 8 5/8" @ 217 w/175, Geol Steve Kriedler
DST 1 (NEVA-ADM) 708-745, op30, si30, op30, si30,
Rec 10' Mud, ISIP 38, FP 23-23/23-23, FSIP 38, BHT
74
DST 2 (CAT) 3085-3101, op30, si30, op30, si30, Rec
mud in tool, ISIP 4, FP 0-4/4-4, FSIP 4, BHT 101
RTD 3250, 4 1/2" @ 3249 w/75
Perf (MISS) 3206-12, 3216-22, 2100 Gal 15% A, fract
w/901 BW + 30,000 sd
IPP 5 BOPD + WTR, MISS 3206-22 OA
COMPLETED 8-13-79

KB LOG TOPS:
NEVA 510 + 700
ADMIRE SD 736 + 474
HOWARD 1160 + 50
TOPEKA 1337 - 127
PEACOCK 1545 - 335
HOOVER LM 1826 - 616
LATAN 2049 - 839
STALNAKER 2075 - 865
PERRY LM 2277 - 1067
PERRY SD 2292 - 1082
LAYTON 2522 - 1312
(CON'T FOR TOPS)

Petroleum Information Corporation
COPYRIGHTED 1979 REPRODUCTION PROHIBITED

RECEIVED STATE CORPORATION COMMISSION

AUG 13 1991

COMPLETION DIVISION Wichita, Kansas

KANSAS CITY 2668 - 1458
B/KANSAS CITY 2796 - 1586
OSWEGO 2875 - 1665
CHEROKEE 2989 - 1779
CATTLEMAN 3083 - 1873
BARTLESVILLE 3176 - 1966
MISS CHERT 3206 - 1996
MISS CHERT PORO 3216 - 2006
MISS LM 3222 - 2012
LTD 3250 - 2040
RTD 3250 - 2040
TD IN MISS

COMP ISSUED 8-21-79

all be trans- Conservation, please note