

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33235
Name: Chieftain Oil Company
Address 1: P.O. Box 124
Address 2: _____
City: Kiowa State: KS Zip: 67070 + _____
Contact Person: Ron Molz
Phone: (620) 825-4030
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: 4412 Bottom: 4422 T.D. _____
_____ Depth to Top: 4426 Bottom: 4432 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 4943

API No. 15 - 007-23417-0000
Spot Description: _____
NW NE NE SW Sec. 4 Twp. 32 S. R. 10 East West
2,416 Feet from North / South Line of Section
2,085 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barber
Lease Name: Rowe A Well #: 1
Date Well Completed: _____
The plugging proposal was approved on: 01/10/12 (Date)
by: Kenny Sullivan (KCC District Agent's Name)
Plugging Commenced: 1/9/12
Plugging Completed: 1/11/12

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	348	0
		Casing	5 1/2	4937	3100

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 4360', dump 2sx cement with dump bailer on bridge plug, lay down casing, run tubing to 1st plug at 600', pump 10sx gel and 50sx cement 60/40 POZ, 2nd plug at 378', spot 50sx cement, 3rd plug at 60', circulate to surface with 30sx.

RECEIVED
JAN 18 2012
KCC WICHITA

Plugging Contractor License #: 5105 Name: Clarke Corporation
Address 1: P.O. Box 187 Address 2: 107 W. Fowler
City: Medicine Lodge State: KS Zip: 67104 + _____
Phone: (620) 886-5665
Name of Party Responsible for Plugging Fees: Chieftain Oil Company
State of Kansas County, Barber, ss.
Mark Morgenstern Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenstern

AP