

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34470
Name: Victory Minerals LLC
Address 1: P O Box 414931
Address 2: _____
City: Kansas City State: MO Zip: 64141 + _____
Contact Person: Carmon Decker
Phone: (816) 223-3712
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 2980 Bottom: 3090 T.D. 3100
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 035-22896 • 00 • 00
Spot Description: SE-SW-NW-SW
SE SW NW SW Sec. 32 Twp. 33 S. R. 6 East West
1,650 Feet from North / South Line of Section
4,620 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Cowley
Lease Name: Berry Well #: 11
Date Well Completed: 9-16-1981
The plugging proposal was approved on: 1-13-2012 (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 1-17-2012
Plugging Completed: 1-18-2012

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------------|---|-------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | surface | 8.625 | 200 | 0 |
| Mississippi | oil and water | long string | 4.5 | 3090 | 0 |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cornish Wireline Services perforated two holes in the casing at 350' on 1-17-2012 and then set a CIBP at 360' also on 1-17-2012. Gressell Oil Field Services ran 1" spool pipe to 360' and we started pumping in cement. We filled the casing and circulated cement to surface and also circulated cement to surface in the annuals of the surface casing and long string. Gressell Oilfield Services work ticket #38861 using 125 sacks of cement.

Plugging Contractor License #: 34470 99998 Name: Victory Minerals LLC
Address 1: P O Box 414931 Address 2: _____
City: Kansas City State: MO Zip: 64141 + _____
Phone: (816) 223-3712
Name of Party Responsible for Plugging Fees: Victory Minerals LLC
State of Kansas County, Cowley, ss.
Carmon Decker Bonanno Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Carmon Decker Bonanno

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

JAN 23 2012

KCC WICHITA