

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-101-20193-0000

LEASE NAME Case A #1

WELL NUMBER \_\_\_\_\_

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

SEC. 6 TWP. 17 RGE. 28w (E) or (W)

COUNTY Lane

Date Well Completed \_\_\_\_\_

Plugging Commenced 12/23/86

Plugging Completed 1/6/87

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Donald C. Slawson

ADDRESS 200 Douglas Bldg. Wichita, Ks. 67202

PHONE# (316) 263-3201 OPERATORS LICENSE NO. 5181

Character of Well \_\_\_\_\_

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	281'	none
				4 3/4"	4649'	1375'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4280' & 4 sacks cement. Shot pipe at 2521', 2218', 2011', 1810', 1612', & 1406'. Pulled 42 joints of pipe. Plugged well with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug, & 150 sacks 60/40 poz 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 13th day of January, 19 87

James Hoover  
 Notary (Public Corporation Commission)

My Commission Expires: \_\_\_\_\_



1-14-87  
 JAN 14 1987  
 Form CP-4  
 Revised 07-86  
 CONSERVATION DIVISION  
 Wichita, Kansas

# DONALD C. SLAWSON WELL RECORD

15-101-20193-0000


LEASE Case 'A' Well No. 1  
 OPERATOR DONALD C. SLAWSON & Bill Porter  
 LOCATION NW NE NW  
 SECTION 6 TWP 17 RANGE 28W  
 SURVEY \_\_\_\_\_ BLOCK \_\_\_\_\_ SECTION \_\_\_\_\_  
 COUNTY Lane STATE Kansas  
 STAKED BY Glen Conway DATE 9/29/76 ELEVATION 2786 K.B.

TOOLS	STARTED	COMPLETED	FROM	TO	CONTRACTOR
ROTARY	10/1/76	10/13/76	0	4650	Chief Drilling Co., Rig No.1
COMPLETION	10/19/76	10/22/76			Cheyenne Well Service

OPEN HOLE LOGS Petro Log GR-N-Guard Sonic Caliper FORMATION  
 COMPLETION INTERVALS Perfs 4332-37' Marmaton Lime  
PBTD 4590

### CASING, TUBING AND RODS

JOINTS	SIZE	WT	COUPLING	GRADE NEW/USED	SETTING DEPTH	CEMENT		REMARKS
						SACKS	EST. TOP	
7	8-5/8	28	ST&C	New	281	225	Gr.	
67	4-1/2	10.5	ST&C	Scotch-K	2177			
60	4-1/2	10.5	ST&C	K-35 New	4649	150		
140	2-3/8"	4.7		New	4331	with 13	68'	mud anchor
172	3/4"	11.78		new rods 1-6'; 1-2'; 3/4" pony rods				
2"x1 1/2"x12' metal stroke through pump 16 ft x 1 1/2" polish rod								

### STIMULATION RECORD

Treatment	acid	acid
Frac / Acid		
Date	10/20/76	10/21/76
Quantity (Gals.)	250	1250
Type	NE-15	NE-28
Proppant		
Tubing / Casing	Casing	Casing
Breakdown Pressure	50	0
Treat Pressure	50-125	400-500
Instant SIP	100	350
Total Bbls. Load	75	110
Flush Agent	water	water
Oil/Gas Before	1BPH	4BPH
Oil/Gas After	4 BPH	32 BPH
Water Before	trace	trace
Water After	trace	trace
Done By	Halliburton	Halliburton

### PUMPING UNIT

Manufacturer Parkersburg  
 Size 540 H80D  
 Serial No. 44610  
**PRIME MOVER**  
 Manufacturer Wagner  
 Size 15 HP  
 Serial No. G3M10304

### TANK BATTERY

1-10x15 steel gunbarrel new  
 2-12x10 steel stock tanks new  
 100' 2" PVC leadline

Initial Potential (Date) \_\_\_\_\_ (BOPD/MMCFPD) \_\_\_\_\_ (% Water) \_\_\_\_\_