



15-169-20087-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

August 22, 1978

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Willard Brucker of Blackstone Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Brucker guarantees payment of the plugging fee.

Operator's full Name: Brandt Oil Company

Complete Address: 1103 Douglas Bldg, Wichita, Kansas

Lease Name: Carlin Well No. 1

Location: SW SE NE Sec. 8 Twp. 15 Rge. 3 (SW) X

County: Saline Total Depth 3470 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Brucker was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/2 sack hulls to 250' and cement hole with 25 sacks cement through drill pipe. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks cement. 8 5/8" - 339' - Cement Circulated

Very truly yours, 08-25-1978

CONSERVATION DIVISION  
Wichita, Kansas

[Signature]  
Conservation Division Agent