



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Rice of Sterling Drilling Company has this date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Dorchester Exploration, Incorporated,

Complete Address: 1204 Vaughn Building, Midland, Texas.

Lease Name: Miller Well No. I

Location: CNW/4 Sec. 11 Twp. 19 Rge. (E)(W) 40

County: Greeley Total Depth 2908' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

375'--10 3/4" Surface casing, cement circulated with 300 Sx.

Circulate hole with heavy mud. Pull DP to 1175' and displace 110 Cu. Ft. cement thru DP. Pull DP to 400' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge 0-40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent