



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Dore has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Dore Gas Inc.

Complete Address: Box 544, Liberal, Kansas

Lease Name: Plunkett Well No. 1

Location: C SW NE Sec. 7 Twp. 22 Rge. 42 NE (E) (W)

County: Hamilton Total Depth 2750' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 160' circulated w/ cement. 4 1/2" to 2750' cemented.

Top perforations 2678' Plug bottom w/ 15 sacks cement.

Top of cement. 2550' Mud 2650' to 600'

Spot 35 sacks cement 600' to 500' Mud 500' to 200'

Spot 35 sacks cement 200' to 100' Mud 100' to 45'

Plug, Pulls w 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent