



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 26 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Spaugh of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Spaugh guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg.. Wichita, Kansas

Lease Name: Blanche Smitherman Unit Well No. 1

Location: C SW NE Sec. 13 Twp. 22 Rge. 42 (E) (W)

County Hamilton Total Depth 2674' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Spaugh was instructed to plug the well as follows:

7"-244' Circulated w/cement. 4 1/2"-2640' Circulated w/cement.


Perforations 1650' to 2626'

25 Sax.cement 2666' to 2340' Mud 2340' to 1700'

15 Sax.cement 1700' to 1520' Mud 1520' to 400'

35 Sax.cement 400' to surface. No pipe pulled. Halliburton Cem.Co.

Very truly yours,


 Conservation Division Agent