



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 21 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Stewabb of C.I.G. has this date requested permission to plug the following described well:

Mr. Stewart guarantees payment of the plugging fee.

Operator's full Name: Colorado Interstate Gas Company

Complete Address: Box 1087, Colorado Springs, Colorado

Lease Name: Cornwell Well No. 1

Location: C SW Sec. 12 Twp. 26 Rge. 43 (E) (W)

County: Hamilton Total Depth 2861' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Stewart was instructed to plug the well as follows:

o 5/0" to 789' circulated w/ cement. 5 1/2" to 2830' cemented,

Top perforations 2757' Plug bottom w/ 25 sacks cement.

Top of cement 1280' Mud 1280' to 700'

Spot 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent