



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

May 1, 1969

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 16 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Art Lamb of Art Lamb Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Cal Jones

Complete Address: Canton, Kansas 67428

Lease Name: Petersen "B" Well No. 1

Location: C SE NE Sec. 20 Twp. 14 Rge. 2 (E)(W) X

County: Saline Total Depth 3276' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lamb was instructed to plug the well as follows:

Fill hole with sand to 3250' and cement with 6 sacks cement.

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and cement

hole with 30 sacks cement. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 15 sacks cement.

Very truly yours,

Conservation Division Agent